PLEASE TAKE NOTE OF THE FOLLOWING PROCESSES REQUIRED FOR MHA AND ANTENNA SWAPS

1. Book on site with MBNL permit but DO NOT lock down;

2. Call SOG support to let them know that you intend to swap MHAs;

3. Call MBNL and lock down site;

4. Swap antennas and MHAs;

5. Call MBNL to bring the power back on;

6. Call SOG support to reconfigure the MHAs.

This process must be adhered to at all times.
We cannot remove existing equipment without using an outage.
If this happens, we may be forced to remove teams from the project.