CUSTOMER:
ANDRITZ SCA



PROJECT:
Helios debarking drum production

WHERE:
Hanko, Finland

INVOLVED PERSONNEL:
Steel construction fitters and welders

PERIOD:
2013 - 2016

SCOPE OF WORKS:
1. Assembly of half rings (Ø 5,6 m) into single rings;
2. Welding works (SAW and MAG process);
3. Assembly of welded rings into complete construction: length - 39 m; weight - 299309 kg;
4. Testing works;
5. Painting works.



























